### **Detailed Field Test Summary**

The TransTech Joint Maker<sup>TM</sup> System can deliver higher density, higher quality longitudinal joints!

**THE CHALLENGE**: Pavement owners are instituting longitudinal joint density performance specifications on a more frequent basis. Warranties for longitudinal joint performance also are being included in a variety of new contract structures, including warranty, A+B, and Design/Build.

**RESULTS:** In recent pavement field tests, the TransTech Joint Maker<sup>TM</sup> System constructed longitudinal joints yielding average densities at the joints which are comparable to, and in come cases meet or exceed the average densities of the asphalt mat. In all cases, the agency having jurisdiction for the project sanctioned the test results.

1996 Field Test Summary					
	_		Average Density		
<u>State</u>	Pavement Type	Mat	<u>Joint</u>	<u>Difference</u>	
Maine	Highway	92.0%	93.8%	+1.8%	
Indiana	Highway	94.1%	94.1%	+0.0%	
Indiana	Airport	97.6%	96.4%	-1.2%	
Pennsylvania	Highway	94.0%	93.0%	-1.0%	
Pennsylvania	Airport	97.4%	96.6%	-0.8%	
Louisiana	Airport	99.3%	97.0%	-2.3%	
New York	Airport	99.2%	97.3%	-1.9%	
Indiana	Airport	97.4%	95.8%	-1.6%	
1997 Field Test Summary					
		Average Density			
<u>State</u>	Pavement Type	Mat	<u>Joint</u>	Difference	
Puerto Rico	Airport	100.0%	98.3%	-1.7%	
Florida	Airport	98.1%	96.9%	-1.2%	
Manitoba, Canada	Highway	94.8%	94.1%	-0.7%	

Longitudinal joints made with the Joint Maker<sup>TM</sup> System:

- Meet or exceed performance specifications, while lowering the cost of paving!
- Increase pavement life and reduce maintenance costs!
- Improve work site safety and public convenience!

<u>Project:</u> State of Maine Department of Transportation

USA Route 1A, Caswell

Project 96-02

<u>Date Paved:</u> September 1996

Asphalt Mix: Type C Contractor:

<u>Highway Type:</u> Two Lane, Width 10' 9" Lane Construction

Mat Thickness: 1.25"

Project consisted of six 2,000' test sections. The Joint Maker<sup>TM</sup> was used on one section. The other sections consisted of various rolling techniques, edge cutbacks, and a control section.

**Summary Results:** Average Density Difference: +1.8%

<u>Project:</u> Indiana Department of Transportation

I-70, Hancock County, Indiana

Contract # R-22232

<u>Date Paved:</u> June 1996

Asphalt Mix: #11 Surface Contractor:

Highway Type: Interstate Milestone Contractors

Mat Thickness: 1.00"

First warranty contract in the State of Indiana. Five year warranty on pavement, including longitudinal joints. Repaving consisting of milling existing HMA, crack and seat of concrete, new binder course, and new surface course.

Summary Results: Average Density Difference: +0.0%

Project: Niagara Falls International Airport

Mat:

Niagara Falls, New York

Date Paved: August - September 1996

Asphalt Mix: P-401 Contractor:

Janik Paving & Construction Highway Type: Airport Runway

Mat Thickness: 2" - 4"

Project was paved in two phases, the first without the Joint Maker<sup>TM</sup>, and the second with

the Joint Maker<sup>TM</sup>.

Without JM With JM 99.2% 98.8% Joint: 94.6% 97.3%

**Summary Results:** Average Density Difference with JM: -1.9%

Average Density Difference without JM: -4.2%

Purdue University Airport Project:

West Lafayette, Indiana

Project 16232

Date Paved: July – August 1996

P-401 Asphalt Mix: Contractor:

Main Runway 10-28 Highway Type: Milestone Contractors

Mat Thickness: 2.5" Base, 1.5" Top

Existing runway was pulverized, compacted and left in place as sub-base. New base

course and top course added, 150" wide x 4600' long.

**Average Density Difference: -1.6% Summary Results:** 

Project: U.S Army Reserve Aviation Facility

Johnstown, PA

<u>Date Paved:</u> August 1996

Asphalt Mix: HD Intermediate Course <u>Contractor:</u>

HD Wearing Course - Apron

<u>Airport Type:</u> Aircraft and Helicopter Quaker Sales Corp.

Parking Area

<u>Mat Thickness:</u> 2" intermediate – Parking

2" wearing - Apron

Project was a new installation, with a new stone base under the entire area. The job size was approximately 700' x 700'.

Summary Results: Average Density Difference: -0.8%

Project: New Orleans International Airport

New Orleans, Louisiana Project N.O.A.B. #55-92-07

Date Paved: May – October 1996

Asphalt Mix: P-401 Contractor:

Highway Type: Airport Taxiway T.L. James & Co.

Mat Thickness: 3"-5"

Project was paved in two phases, the first without the Joint Maker<sup>TM</sup>, and the second with

the Joint Maker<sup>TM</sup>.

 Without JM
 With JM

 Mat:
 99.0%
 99.3%

 Joint:
 95.9%
 97.0%

Summary Results: Average Density Difference with JM: -2.3%

Average Density Difference without JM: -3.1%

Project: Richmond Municipal Airport

Richmond, Indiana AIP # 3-18-0071-03

Date Paved: July 1996

Asphalt Mix: P-401.75 Contractor:

<u>Airport Type:</u> General Aviation Milestone Contractors

Runway Overlay

Mat Thickness: 1.75" – 3.0"

Resurfacing of main runway and aircraft parking area. Density results obtained by coring by Engineering and Testing Services, Inc. Total of 152 cores taken.

**Summary Results:** Average Density Difference: -1.2%

<u>Project:</u> Commonwealth of Pennsylvania

Department of Transportation

Pouts SP 441 South of Harrish

Route SR-441, South of Harrisburg

Project # 087302

<u>Date Paved:</u> September 1995

Asphalt Mix: 1D-2 Contractor:

<u>Highway Type:</u> Two lane McMinn's Asphalt

13' width; 6" shoulder

Mat Thickness: 1.50"

Resurfacing project contained eight longitudinal joint construction test sections, each 500' in length. Density results were obtained using Nuclear Gage. Sample size: 18 per test section

**Summary Results:** Average Density Difference: -1.0%

Project: Luis Munoz Marin International Airport

San Juan, Puerto Rico

Runway 8-26

BlawKnox PF-180 Paver with 8" Joint Maker<sup>TM</sup> System

<u>Date Paved:</u> May – July 1997

<u>Contractor:</u> Betteroads Corp.

Lot Number	Avg. Mat Density	Avg. Joint Density	Lot Number	Avg. Mat Density	Avg. Joint Density
1	98.3	98.1	11	99.9	97.7
2	101.5	98.5	12	99.8	98.6
3	100.5	99.2	13	99.8	98.3
4	100.0	98.7	14	100.0	98.8
5	100.0	98.4	15	100.4	98.1
6	100.2	98.7	16	99.8	97.3
7	99.1	98.7	17	99.8	96.8
8	100.1	98.5	18	99.7	97.9
9	100.4	99.4	19	100.3	98.2
10	100.3	97.9	20	100.3	97.5

Total Average Mat Density: 100.0 Total Average Joint Density: 98.3

**Summary Results:** Average Density Difference: -1.7%

Project:	RSW Air Carrier Apron Rehabilitation Fort Myers, FL				
Date Paved:		May – June 1997		Contractor: Betteroads Corp.	
Lot Number	Avg. Mat Density	Avg. Joint Density	Lot Number	Avg. Mat Density	Avg. Joint Density
1	98.8	96.9	16	97.3	97.4
2	97.7	96.2	17	97.7	97.3
3	97.3	96.3	18	97.9	96.7
4	98.6	97.5	19	97.9	97.6
5	98.2	97.4	20	98.5	97.7
6	99.6	97.5	21	98.0	97.6
7	98.2	97.4	22	98.8	99.0
8	97.9	97.3	23	97.4	96.1
9	97.9	97.3	24	97.4	96.0
10	97.3	95.1	25	97.3	95.6
11	97.3	96.4	26	97.3	95.6
12	97.6	95.9	27	97.2	95.6
13	96.6	96.6	28	97.2	95.7
13S	97.7	96.6	29	97.4	95.6
14	99.9	98.2			
15	97.8	96.1			

Total Average Mat Density: 98.1 Total Average Joint Density: 96.9

**Summary Results:** Average Density Difference: -1.2%

Project:		Provicinial Road 354 Construction Manitoba, Canada		
Date Paved:	June 1997	<u>Contractor:</u> Nelson River Construction		
With 8" Joint Maker	<u>Kilometer</u> 3 4 5 6	Avg. Mat Density 94.1 95.1 94.9 95.1	Avg. Joint Density 93.8 94.0 94.2 94.5	
Total Average Density:		94.8	94.1	
Without 8" Joint Maker	12 11 10 9	94.4 94.4 94.5 94.3	92.7 92.8 92.5 92.6	
Total Average Density:		94.4	92.6	
Summary Results: Average Density Difference with JM: -0.7% Average Density Difference without JM: -1.8%				